8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

| Items of work | Per | Quantity |
|---|---|---|
| Earthwork hard soil ... ... ... ... ... | C. yd. | 18 |
| Burnt brick in mud ... ... ... ... | C. ft. | 750 |
| Do in mortar ... ... ... ... | " | 459 |
| Burnt stone slabs roughly dressed 6" thick and filed ... ... ... | S. yd. | 195 |
| Chunam plastering ... ... ... ... | Sq. | 15·51 |
| Honne wood work wrought and put up ... ... ... | C. ft. | 41·62 |
| Roofing with 1st class Mangalore tiles with teak reepers, etc., complete ... | Sq. | 8·07 |
| Ridge tiles set in mortar ... ... ... ... ... | R. ft. | 25 |
| Honne wood eave board ornamental 9" depth ... ... | " | 49 |
| Chunam borders 9" width, 6" height with plastering. ... ... ... | " | 55 |
| Flooring with Cuddapah slabs over 3" concrete and cement pointing ... ... | Sq. | 7·32 |
| Doors honne wood battened including frames 4"×3" hinges, etc., complete (shutters 1¼" thick.) | S. ft. | 105 |
| Windows honne wood battened including iron bars ⅜" diameter frames 3"×4", etc., complete (6 bars to each). | " | 33 |
| White and colourwashing ... ... ... ... ... | Sq. | 6·91 |
| Tarring the wood work ... ... ... | L. S. | ..... |
| Ventilating tiles ... ... ... ... | Each | 4 |
| Curving the room corners with chunam ... ... ... | L. S. | ..... |
| Inserting bond stones for connecting the old work with new buildings ... | Each | 6 |
| Painting with wood oiling, etc., (honne wood) ... ... ... | L. S. | ..... |
| Clearing site and levelling the ground ... ... ... ... | " | ..... |
| Fixing new doors in the portion walls including making openings ... | Each | 2 |
| Cutting groves in stone up rights ... ... ... ... | " | 3 |
| Providing black boards ... ... ... ... ... | No. | 2 |

A. PUTTUSAMAIYA,
*Executive Engineer.*

## SHIMOGA DIVISION.

*Abstract Notification.*

The attention of the public is invited to the notification calling for tenders published in page 5, Part IV of the *Mysore Gazette*, dated 18th December 1918, for "Constructing Masonry Aqueducts" for the high level channel under the Sowlanga Tank in Honnali Taluk.

K. NARAYANA IYENGAR,
*Offg. Executive Engineer.*

## BHADRA ANICUT RANGE.

*Abstract Notification.*

The attention of the public is invited to the Notification dated 11th December 1918, in pages 1114 and 1115 of Part IV of the *Mysore Gazette*, wherein tenders for constructing an anicut across the river Bhadra near Gopala has been called for.

V. K. KUNTE,
*Temporary Engineer, Gopala Anicut Range, Benkipur.*

# MEDICAL DEPARTMENT.

## VICTORIA HOSPITAL, BANGALORE.

NOTICE.

Tenders are invited for the supply of diet articles, etc., to the Victoria Hospital, Bangalore, for six months, from 1st March 1919 to 31st August 1919, *vide Mysore Gazette*, dated 2nd January 1919, or apply to the undersigned for further particulars.

H. B. MYLVAGANAM,
*Medical Officer in charge.*

## MEDICAL STORES.

*Abstract Notification dated 9th January* 1919.

Notice is hereby given that sealed tenders will be received up to the 31st January 1919, by the Superintendent, Medical Stores, Mysore Government, Bangalore, for the supply, by contract, of country medicines, stationery articles, etc., to the Government Medical Stores from 1st March 1919 to 31st August 1919 (both days inclusive).

For further particulars, reference is invited to the detailed notification published in the issue of the *Mysore Gazette*, dated 2nd January 1919.

V. ABBOY NAIDU, L.M. & S.,
*Superintendent, Medical Stores.*